






# ALMA Project Status

Adrian Russell



# Where is ALMA?







ALMA





# What is ALMA?

Baselines from 15m to 15km

5000m site in Atacama desert

Receivers: low-noise, wide-band (8GHz), dual-polarisation, SSB

Digital correlator,  $\geq 8192$  spectral channels, 4 Stokes

Sensitive, precision imaging between 30 and 950 GHz

350 GHz continuum sensitivity: about 1.4mJy in one second

Angular resolution will reach  $\sim 40$  mas at 100 GHz (5mas at 900GHz)

First light system has 6 bands: 100, 230, 345 and 650GHz

Japan will provide 140, 460 and 900GHz

*10- 100 times more sensitive and 10- 100 times better angular resolution compared to current mm/submm telescopes*



# ALMA Construction

ALMA construction has started in earnest

North America and ESO have each placed contracts for at least 25 antennas; Japan has a contract for three 12m antennas (with the remaining 12m and 12 x 7m antennas to follow)

Site construction has started both on the mid-level Observation Support Facility (OSF) and on the Array Operations Site technical building (AOS) at the 16,500 foot site itself

The road to the site is over 85%percent complete







# ALMA Status

ALMA has just undergone a major rebaselining and subsequent review

The review declared the technology readiness of ALMA very high and judged that most technical risk has been eliminated

Five years ago ALMA was a "must do" scientifically but with high technical risk pushing the state of the art



We now have:

- prototype antennas that meet ALMA's demanding requirements
- receivers with near quantum-limited performance, unprecedented bandwidth and no mechanical tuning

- the first quadrant of the correlator completed below cost and with enhanced performance

The baseline includes appropriate contingency for remaining technical risks (e.g. photonic local oscillator, cold multipliers, ortho mode transducers)







# Latest update...

Progress continues to be excellent

## Highlights

Completion of Contractors Camp

Start of ASO- TB work


Prototype Systems Integration started in Socorro

Contract signed for the antenna transporters

ASIAA, Taiwan has entered the ALMA project through the signing of an agreement with ALMA- Japan

ESO Council reconfirmed scientific imperative and affordability of ALMA

**Review of the rebaselined ALMA budget noted that "the science capability of the array was extremely exciting, and that ALMA remains an extremely exciting project for the future"**



2005/11/30









